



Avon Conservation Commission
65 East Main St
Avon, MA 02322

Town of Avon, MA Conservation Commission
Wetlands Bylaw Standard Conditions (ASC)

Project Location:
Proposed Project:
DEP File #:

ASC1 – Avon Form 1 and Form 2 shall be filled out and submitted to the Commission before the start of any construction.

ASC2 - Avon minimum standard for erosion control is Silt fence not dug in, but the flat lay on the ground and staking a silt sock on top 6" Silt Sock, erosion controls are to remain in place until disturbed area have revegetated and stabilize.

ASC3- 48 hour notice prior to installation of erosion control is to be made to the Commission for inspection of erosion control.

ASC4 - Keep a clean site. Maintaining dust control shall be done with water. All granular materials stored on-site must have erosion & dust controls maintained throughout the construction.

ASC5 - Anything that falls onto the street is to be clean up immediately.

ASC6 - Photographs of the project area shall be taken A) Prior to work, B) During the main construction and C) After the work is completed. The applicant shall supply a copy of the photographs with their request for Certificate of Compliance.

ASC7 – The Certificate of Compliance shall be requested as soon as practical after the work is complete and the undisturbed area have stabilized. After the Certificate is issued, the DEP sign with the project number is to be removed.

ASC8: - The commission approves the building of a retaining wall to be erected within 50' and within 25' of the resource area. The Commission approves the improvements to the stormwater onsite and including improvements to adjacent sites as mitigation for the building of the retaining wall within 25' of the resource area.

ASC9 – The Commission approves the disturbance within the buffer zone of up to 2,600 SF, excavation of up to 150 CY of earth and up to 150 CY of fill. Within the buffer zone and within 25' of the resource area.