

Avon Conservation Commission 65 East Main St Avon, MA 02322

Town of Avon, MA Conservation Commission Wetlands Bylaw Special Conditions (ASC)

Project Location: Proposed Project: DEP File #: N/A (RDA)

- ASC1 Avon Form 1 and Form 2 shall be filled out and submitted to the Commission <u>before</u> the start of any construction.
- ASC2 Avon minimum standard for erosion control is Silt fence not dug in, but the flat lay on the ground and staking a silt sock on top 6" Silt Sock, erosion controls are to remain in place until disturbed area have revegetated and stabilize.
- ASC2 Avon minimum standard for erosion control is 6" Silt Sock, erosion controls are to remain in place until disturbed area have revegetated and stabilize. Erosion control is to stay in place until vegetation has stabilized all disturbed soils.
- ASC3 48 hour notice prior to installation of erosion control is to be made to the Commission for inspection of erosion control.
- ASC4 Keep a clean site. Maintaining dust control shall be done with water. All granular materials stored on-site must have erosion & dust controls maintained throughout the construction.
- ASC5 Anything that falls onto the street is to be clean up immediately.
- ASC6 Photographs of the project area shall be taken A) Prior to work, B) During the main construction and C) After the work is completed. Photographs are to be submitted to the Commission after the work is completed and the disturbed areas have revegetated.
- ASC7: The commission approves the building of a retaining wall to be erected within 50' and within 25' of the resource area. The Commission approves the improvements to the stormwater onsite and including improvements to adjacent sites as mitigation for the building of the retaining wall within 25' of the resource area.
- ASC8 The Commission approves the disturbance within the buffer zone of up to 2,600 SF, excavation of up to 150 CY of earth and up to 150 CY of fill. Within the buffer zone and within 25' of the resource area.